

---

---

**Subject: Notice inviting quotations for extending the corridor floor area by providing & fixing MS Base frame at first floor of Science explorium building at PGSC Kapurthala**

Sealed Quotations are invited from experienced vendors/firms for the subject cited work as per details given below so as to reach the office of Director, Pushpa Gujral Science City, Kapurthala on or before \_\_\_\_\_ up to 2:30 pm. The sealed quotations will be opened on same day at 3:00pm in presence of respective firms/agencies/ contractors who may like to be present at the time.

| S.no | Item Description  | Unit | Qty  | Rate (In Rs.) | Amount (In Rs.) |
|------|---|------|------|---------------|-----------------|
| 1.   | Structural steel work in angles, tees, flats, riveted, Including cutting, fixing all gusset plates, bolts, nuts, rivets etc. with hoisting and erecting in position.<br>(a)For roof truss, well curbs, plate girders etc. of any span for building for bridges up to 15M span.<br>Complete in all respects as per attached Drg. No012786-87&88.<br><b>CSR 18.3(a)</b> | Qtl  | 6.76 |               |                 |

|    |  |             |    |               |  |
|----|--|-------------|----|---------------|--|
| 2. | Cutting & Fixing of the Existing railing on the frame as on S.no.1. & Complete in all respects as per attached drg no. No012786-87&88  | Lump<br>Sum | 01 |               |  |
| 3. | Applying priming coat with metal primer on new steel or iron work including preparation of surface.<br><b>CSR 16.20</b>  | SqM         | 34 |               |  |
| 4. | Painting two or more coats excluding priming coat with synthetic enamel paint in all shades on wood work, metallic or plastered, concrete surface to give an even shade.<br><b>CSR 16.17</b> | SqM         | 34 |               |  |
|    |  |             |    | Taxes(if any) |  |
|    |  |             |    | Total         |  |
|    | (Total In Words)   |             |    |               |  |

**Terms & Conditions:**

1. The work will be executed as per attached drawing.
2. PGSC reserves the right to accept or reject the offer without assigning any reason.
3. All the tools like welding set spanners, scalf- folding, ropes, chains, ladders etc required for executing the work at the site should be arranged by the contractor.
4. **Payment terms**
  - a. No Advance payment will be given.
  - b. 100 % payment will be released after the completion of work to the satisfaction of PGSC authorities.
  - c. Bill may please be raised in the name of Pushpa Gujral Science City, Kapurthala.

- d. Quantity may increase or decrease as per requirement of the work & payment will be done as per actual measurements at site.
  - e. Taxes & Govt. levies if any will be deducted as per rules.
5. Agencies /contractors are advised to visit the site before submitting the quotation.
  6. All the MS material used should be ISI Marked.
  7. There should be no traces left after shifting the railing to the proposed site & everything should be completed in all respects.

### **Completion Period**

8. The Work in all respects should be completed within 15 Days from the date of the issuance of the work order.

### **9. Compensation for the delay**

If the contractor fails to maintain the required rate of progress or to complete the work & clear the site on before the contract or extended date of completion, he shall without prejudice to any other right or remedy available under the law ,pay compensation the amount calculated at the rates stipulated below or such smaller amount as The Director may decide (whose decision in writing shall be final & binding) on the amount of the tendered value of the work for every completed day / week (as applicable) that the progress remains below or that the work remains in incomplete. Completion period not exceeding 3 months (stipulated) @ 1% per week or part thereof provided always that the total amount of compensation for delay to be paid under this condition shall not be exceed 5% of tendered value of work.

### **10. JURISDICTION**

The legal jurisdiction shall be district courts at Kapurthala.

Administrative officer  
PGSC, Kapurthala